

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-083-21560-00-00
Spot: NESE Sec/Twnshp/Rge: 25-21S-22W
2016 feet from S Section Line, 683 feet from E Section Line
Lease Name: HAHN Well #: 1
County: HODGEMAN Total Vertical Depth: 4487 feet

Operator License No.: 5663
Op Name: HESS OIL COMPANY
Address: PO BOX 1009
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	260		WITH 175 SX CMT
DVT		1427		WITH 380 SX CMT
PROD	5.5	4472	0	WITH 175 SXC MT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/09/2010 9:00 AM
Plug Co. License No.: 5663 Plug Co. Name: HESS OIL COMPANY
Proposal Rcvd. from: ARNIE HESS Company: HESS OIL COMPANY Phone: (785) 731-5615

Proposed Plugging Method: PUMP 300# HULLS- 30 SX CMT - GEL SPACER TO 1427'. CMT FROM 1427'-0'. 100 SX CMT TO CHECK 8 5/8" X 5 1/2".

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/09/2010 1:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4455' & PUMP 25 SX GEL, 30 SX CMT, & 100# HULLS. PULLED TBG TO 1440;' & PUMPED 190 SX CMT. CMT CIRCULATED. PULLED TBG & TOPPED OFF WITH 10 SX CMT. TIED ONTO BACKSIDE & PUMPED 20 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4438	4444		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed

Michael Maier
(TECHNICIAN)

RECEIVED
NOV 12 2010
KCC DODGE CITY

RECEIVED
NOV 19 2010
KCC WICHITA

Form CP-20