

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-083-21547-00-00  
Spot: SESENE SW Sec/Twnshp/Rge: 19-21S-22W  
1403 feet from S Section Line, 2853 feet from E Section Line  
Lease Name: LAZORA Well #: 1  
County: HODGEMAN Total Vertical Depth: 4570 feet

Operator License No.: 5663  
Op Name: HESS OIL COMPANY  
Address: PO BOX 1009  
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4505		
SURF	8.625	221		WITH 160 SX CMT
DVT		1462		CEMENTED WITH 175 SX CMT
PROD	5.5	4596	0	WITH 325 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/13/2010 11:00 AM  
Plug Co. License No.: 5663 Plug Co. Name: HESS OIL COMPANY  
Proposal Revd. from: BRYAN HESS Company: HESS OIL COMPANY Phone: (785) 731-5615

Proposed Plugging Method: CHECK RATE. PUMP 200# HULLS WITH 25 SX CMT, MUD SPACER TO 1500'. CMT TO SURFACE FROM 1500'. CHECK BACKSIDE WITH 50 SX CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/18/2010 4:15 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

ESTABLISHED PUMPED RATE OF 1.7 BPM WITH NOT MORE THAN 1500# PRESSURE. PUMPED 150# HULLS WITH 25 SX CMT, MUD SPACER OF 20 SX GEL TO 1500'. CMT FROM 1500'-0' WITH 125 SX CMT. PRESSURED TO 1000# & HELD @ 750#. PRESSURED BACKSIDE WITH 30 SX CMT. 8/18/10: TOC @ 760'. TOPPED OFF PRODUCTION CASING WITH 4 YDS REDI-MIX CMT.

Perfs:

Top	Bot	Thru	Comments
4508	4512		
4496	4501		

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: CSG

District: 01

Signed Eric MacLaren

(TECHNICIAN) RECEIVED

RECEIVED  
AUG 30 2010  
KCC DODGE CITY

SEP 07 2010  
KCC WICHITA

Form CR-24