

TO: ✓  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-02139-00-00  
Spot: SESW Sec/Twnshp/Rge: 17-19S-9W  
662 feet from S Section Line, 3513 feet from E Section Line  
Lease Name: LINK Well #: 1  
County: RICE Total Vertical Depth: 3268 feet

Operator License No.: 9292  
Op Name: SCHECK, TIMOTHY DBA SCHECK OIL  
Address: 211 S FRONT ST  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	234		
PROD	7	3262		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/24/2010 9:30 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: LEON HUXMAN Company: SCHECK OIL OPERATION Phone: (785) 483-0567

Proposed  
Plugging  
Method:

SEE BELOW

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: NONE  
Date/Time Plugging Completed: 11/24/2010 12:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

MIRU-ORIGINAL PLANS WERE TO WORK-OVER WELL TO CLEAN OUT. CASING COLLAPSED @2270'. WELL HAD BEEN SQUEEZED IN 1981 @ 1860' WITH 150 SX'S CEMENT. PERFORATED @ 800' AND 285'. RUN TUBING TO 2260' AND PUMP 50 SX'S CEMENT. PULL TUBING TO 800' AND PUMP 50 SX'S CEMENT. PULL TUBING TO 285' AND CIRCULATE CEMENT TO SURFACE. BACKSIDE CIRCULATED ALSO. PULL TUBING OUT AND TOP OFF. USED 210 SX'S CEMENT.

EMERGENCY PLUGGING REQUEST GRANTED BY DISTRICT SUPERVISOR  
JEFF KLOCK ON 11/24/2010. SEE ATTACHED REQUEST FORM.

Remarks: 60-40 POZ, 4% GEL. ALLIED TICKET #30149. PIONEER WIRELINE TICKET #32333

Plugged through: TBG

RECEIVED  
DEC 03 2010  
KCC WICHITA

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

✓/K