

TO: ✓
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-03611-00-00
Spot: SESWNE Sec/Twnshp/Rge: 17-9S-16W
2970 feet from S Section Line, 1650 feet from E Section Line
Lease Name: DORR Well #: 3
County: ROOKS Total Vertical Depth: 3379 feet

Operator License No.: 6569
Op Name: SCHMITT, CARMEN, INC.
Address: PO BOX 47
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	210	0	w/unknown sxs cmt
PROD	5.5	3377	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/10/2010 2:00 PM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: CURTIS HITSCHMAN Company: SCHMITT, CARMEN, INC. Phone: (620) 793-5100

Proposed Plugging Method: Ordered out 450 sxs 60/40 pozmix - 4% gel - 600# hulls.
Casing parted at 1950'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/10/2010 4:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

LK perforated two holes each at 1260' and 790'.
Ran tubing to 3000'.
Quality Oil Well pumped 150 sxs 60/40 pozmix - 4% gel with 300# hulls.
Pulled tubing to 1903' - pumped 130 sxs cement with 200# hulls.
Pulled tubing to 782' - pumped 50 sxs cement with 100# hulls - cwc.
PTOH. Topped 5 1/2" casing with 10 sxs cement.
Backside full of cement.

Perfs:

Top	Bot	Thru	Comments
3372	3376		
3343	3346		
3314	3318		
3294	3295		
3247	3251		
3235	3243		
3229	3230		
3226	3330		
3195	3198		
3172	3190		

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN)

CM

RECEIVED
NOV 22 2010
KCC WICHITA

Form CP-2/3

NOV 18 2010