

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-04311-00-00

Spot: SWSESE

Sec/Twnshp/Rge: 8-18S-13W

330 feet from S Section Line, 990 feet from E Section Line

Lease Name: JAMISON

Well #: 3

County: BARTON

Total Vertical Depth: 3308 feet

Operator License No.: 33406

Op Name: GARNER, THOMAS

Address: 305 E 7TH
ST JOHN, KS 67576

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3272		
SURF	8.625	743	0	400 SX
PROD	5.5	3295	1720	125 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 10/15/2010 9:00 AM

Plug Co. License No.: 31925

Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Revd. from: TOM GARNER

Company: GARNER, THOMAS

Phone: (620) 549-6618

Proposed
Plugging
Method:

Ordered 350 sxs 60/40 pozmix - 4% gel - 400# hulls.

Plugging Proposal Received By: CASE MORRIS

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 10/15/2010 4:00 PM

KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perfs and topped with 5 sxs cement. Cut casing at 1720'.
Pulled to 1500' - pumped 125 sxs cement with 300# hulls.
Pulled to 750' - pumped 50 sxs cement.
Pulled to 450' - pumped 50 sxs cement.
Pulled to 200' - circulated to surface with 110 sxs cement.
Pulled casing - hole stayed full.

Perfs:

Top	Bot	Thru	Comments
3295	3308		ARBUCKLE
3197	3203		KANSAS CITY

Remarks: QUALITY OIL WELL CEMENTING.

Plugged through: CSG

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

(M)

RECEIVED

NOV 01 2010

Form CP-2/3

OCT 21 2010

KCC WICHITA