

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-00735-00-00  
Spot: SESWSE Sec/Twnshp/Rge: 8-18S-13W  
330 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: KARST Well #: 1  
County: BARTON Total Vertical Depth: 3306 feet

Operator License No.: 33406  
Op Name: GARNER, THOMAS  
Address: 305 E 7TH  
ST JOHN, KS 67576

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3270		
SURF	8.625	744	0	450 SX
PROD	5.5	3294	1780	125 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/18/2010 9:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: TOM GARNER Company: GARNER, THOMAS Phone: (620) 549-6618

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 400# hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/18/2010 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perfs and topped with 5 sxs cement. Cut casing at 1780'.  
Pulled to 1500' - pumped 125 sxs cement with 300# hulls.  
Pulled to 750' - pumped 50 sxs cement.  
Pulled to 450' - pumped 50 sxs cement.  
Pulled to 200' - circulated to surface wit 70 sxs cement.  
Pulled casing - hole stayed full.

Perfs:

Top	Bot	Thru	Comments
3294	3306		ARBUCKLE
3116	3270		KANSAS CITY

Remarks: QUALITY OIL WELL CEMENTING.

Plugged through: CSG

District: 04

Signed Bruce Rodie  
(TECHNICIAN)

CM

RECEIVED

Form CP-2/3

NOV 01 2010

OCT 21 2010

KCC WICHITA