

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-04310-00-00  
Spot: SWSWSE Sec/Twnshp/Rge: 8-18S-13W  
330 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: KARST Well #: 2  
County: BARTON Total Vertical Depth: 3313 feet

Operator License No.: 33406  
Op Name: GARNER, THOMAS  
Address: 305 E 7TH  
ST JOHN, KS 67576

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	754	0	450 SX
PROD	5.5	3304	0	125 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/18/2010 1:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: TOM GARNER Company: GARNER, THOMAS Phone: (620) 549-6618

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 400# hulls - 10 sxs gel.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/18/2010 5:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfed at 1500' - 750' - 400'.  
Ran tubing to 2900' - tied to tubing and pumped 20 sxs gel followed with 50 sxs cement.  
Pulled to 1500' - pumped 75 sxs cement.  
Pulled to 750' - circulated cement to surface with 100 sxs cement.  
Pulled tubing and topped off with 20 sxs cement.  
Max. P.S.I. 250#. Surface pipe full of cement.

Perfs:

Top	Bot	Thru	Comments
3304	3313		ARBUCKLE

Remarks: QUALITY OIL WELL CEMENTING.

Plugged through: CSG

District: 04

Signed Bruce Rodie  
(TECHNICIAN) cm

RECEIVED Form CP-2/3

NOV 01 2010

OCT 21 2010

KCC WICHITA