

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-04312-00-01
Spot: NESWSE Sec/Twnshp/Rge: 8-18S-13W
990 feet from S Section Line, 1650 feet from E Section Line
Lease Name: KARST (ROBINSON) Well #: 4
County: BARTON Total Vertical Depth: 3330 feet

Operator License No.: 33406
Op Name: GARNER, THOMAS
Address: 305 E 7TH
ST JOHN, KS 67576

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	745	0	425 SX
PROD	5.5	3302	1585	125 SX

Well Type: EOR UIC Docket No: E25827.1 Date/Time to Plug: 10/20/2010 7:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: TOM GARNER Company: GARNER, THOMAS Phone: (620) 549-6618

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 400# hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/20/2010 12:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perfs and topped with 5 sxs cement. Cut casing at 1585'.
Pulled to 1500' - pumped 125 sxs cement with 300# hulls.
Pulled to 750' - pumped 50 sxs cement.
Pulled to 450' - circulated and pumped 50 sxs cement.
Pulled to 200' - circulated with 95 sxs cement.
Pulled casing - hole stayed full.

Perfs:

Top	Bot	Thru	Comments
3302	3330		ARBUCKLE
3120	3210		KANSAS CITY

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

OCT 26 2010

RECEIVED ✓

NOV 01 2010

KCC WICHITA

Form CP-2/3