

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-20424-00-00
Spot: SENESE Sec/Twnshp/Rge: 18-22S-9W
1650 feet from S Section Line, 330 feet from E Section Line
Lease Name: DRAKE Well #: 1
County: RENO Total Vertical Depth: 3642 feet

Operator License No.: 33226
Op Name: GIANT HOLDING, LLC
Address: 223 W 4TH
HUTCHINSON, KS 67501

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	213		180 sxs
PROD	4.5	3641		100 sxs

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKES KELSO OIL INC Phone: (620) 938-2943

Proposed Plugging Method: PER KCC RULES

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 09/09/2010 5:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

9/8/2010 SANDED BOTTOM TO 3515' CAPPED WITH 4 SXS OF CEMENT. 9/9/2010 PERFORATED CASING @ 1300', 850', AND 260' WITH LOGGING TRUCK. RAN TUBING INTO 1300' SPOTTED 35 SXS OF CEMENT, PULLED TUBING TO 850' SPOTTED 35 SXS, PULLED TUBING TO 260' PUMPED 110 SXS CEMENT DID NOT CIRCULATE. TAGGED CEMENT AT 863', RAN TUBING BACK IN TO 850' SPOTTED 35 SXS OF COMMON CEMENT 3% CC, PULLED TUBING TO 260' CIRCULATED CEMENT TO SURFACE WITH 100 SXS OF CEMENT. 9/10/2010 CHECKED TOP OF CEMENT, OK.

Perfs:

Top	Bot	Thru	Comments
3615	3630		CSG

Remarks: ALLIED CEMENTING OUT OF RUSSELL TICKET #41980

Plugged through: TBG

RECEIVED

NOV 02 2010

KCC WICHITA

District: 02

Signed

B. J. Hope

(TECHNICIAN)