

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-127-19006-00-00
Spot: NENENE Sec/Twnshp/Rge: 23-16S-9E
4976 feet from S Section Line, 397 feet from E Section Line
Lease Name: VIAR Well #: 1
County: MORRIS Total Vertical Depth: 2943 feet

Operator License No.: 5721
Op Name: GLACIER PETROLEUM CO., INC.
Address: 825 COMMERCIAL ST PO BOX 577
EMPORIA, KS 66801

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	132		75 SX
L1	44.5	2917		285 SX
PROD	7	2942		125 SX
RBP		2800		

Well Type: EOR UIC Docket No: E23863.1 Date/Time to Plug: 11/16/2010 10:00 AM
Plug Co. License No.: 5721 Plug Co. Name: GLACIER PETROLEUM CO., INC.
Proposal Rcvd. from: MARK LYNCH Company: Phone: (620) 342-1148

Proposed Plugging Method: AS PER KCC

Plugging Proposal Received By: JEFF KLOCK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/16/2010 11:00 AM KCC Agent: SHANE JONES

Actual Plugging Report:

11/16/2010 GLACIER RAN TUBING IN AND TAGGED CEMENT FROM PREVIOUS SQUEEZE @ 294'. THEY PULLED BACK UP TO NEXT FULL JOINT. CONSOLIDATED TIED ON AND BROKE CIRCULATION WITH WATER. THEY THEN SWITCHED TO CEMENT AND CIRCULATED 30 SXS FROM 289' TO SURFACE. GLACIER PULLED THE TUBING AND CONSOLIDATED TOPPED OFF HOLE. THEY USED 30 SXS OF 60/40 POS W/4% GEL TK #29987. THE BACKSIDE IS FULL FROM PREVIOUS LINER RUN IN THE HOLE AND NUMEROUS SQUEEZSES IN THE LAST COUPLE OF MONTHS TRYING TO REPAIR WELL. BOTTOM PLUGGED OFF WITH CIBP @2800'.

Perfs:


Top	Bot	Thru	Comments
2942	2943	OH	OPEN HOLE

Remarks: CASING LEAK @ 260', CIBP @ 2800', PLUGGED DUE TO FAILED MIT

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

RECEIVED

DEC 02 2010

KCC WICHITA

Form CP-2/3

SK