

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-20588-00-00
Spot: SESW Sec/Twnshp/Rge: 26-22S-19W
674 feet from S Section Line, 3287 feet from E Section Line
Lease Name: HARRY LEWIS Well #: 1
County: PAWNEE Total Vertical Depth: 4410 feet

Operator License No.: 3972
Op Name: GLENWOOD RESOURCES, INC.
Address: 3440 YOUNGFIELD ST # 278
WHEAT RIDGE, CO 80033

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1215		WITH 525 SX CMT
PROD	4.5	4410	2015	WITH 250 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/08/2010 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: CIBP @ 3915' WITH 2 SX CMT. PLUG AT 1250' WITH 15 SX GEL, 50 SX CMT & 100# HULLS. PLUG AT 600' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: JERRY W. STAPLETON Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/08/2010 11:00 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PUMP 35 SX CMT & 200# HULLS TO BOTTOM. MAXIMUM PRESSURE WAS 800#. SHUT IN PRESSURE 500#. 1ST PLUG PUMPED 15 SX GEL, 50 SX CMT WITH 100# HULLS AT 1250'. 2ND PLUG AT 600' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4353	4357		MISSISSIPPI
3965	3972		LANSING

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

RECEIVED
OCT 22 2010
KCC WICHITA

District: 01

Signed Michael J. Maier
(TECHNICIAN)

RECEIVED
OCT 13 2010
KCC DODGE CITY

Form CD-2/3