

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-00623-00-00
Spot: SWNENE Sec/Twnshp/Rge: 14-20S-12W
4290 feet from S Section Line, 990 feet from E Section Line
Lease Name: BUCKBEE Well #: 1
County: BARTON Total Vertical Depth: 3372 feet

Operator License No.: 6170
Op Name: GLOBE OPERATING, INC.
Address: PO BOX 12
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	323	0	w/unknown sxs cmt
PROD	5.5	3352	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/23/2010 9:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: RICHARD STALCUP Company: GLOBE OPERATING, INC. Phone: (620) 792-7607

Proposed Plugging Method: Ordered 425 sxs 60/40 pozmix - 4% gel - 600# hulls - 13 sxs gel.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/23/2010 1:30 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfed at 1550' - 600' - 320'.
Ran tubing to 3215' - pumped 13 sxs gel - followed with 50 sxs cement and 200# hulls.
Pulled tubing to 1550' - pumped 100 sxs cement with 200# hulls.
Pulled to 700' - circulated to surface with 100 sxs cement and 200# hulls.
Pulled tubing. Tied to casing and pumped 10 sxs cement.
Max. P.S.I. 300#.
Tied to backside - pumped 40 sxs cement.
Max. P.S.I. 250#.

Perfs:

Remarks: QUALITY OIL WELL CEMENTING SERVICE.

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

RECEIVED
DEC 03 2010
12-3-10
KCC WICHITA

Form CP-2/3

NOV 29 2010