

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-21465-00-00
Spot: S2SEW Sec/Twnshp/Rge: 10-22S-12W
2825 feet from S Section Line, 3331 feet from E Section Line
Lease Name: SPANGENBERG Well #: 1-10
County: STAFFORD Total Vertical Depth: 3658 feet

Operator License No.: 6170
Op Name: GLOBE OPERATING, INC.
Address: PO BOX 12
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3600		
SURF	8.625	364		WITH 250 SX CMT
PROD	5.5	3653	1380	WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/23/2010 9:30 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: TIM DICKSON Company: D S & W WELL SERVICING, INC. Phone: (620) 793-5838

Proposed Plugging Method: SAND TO 3300' & 5 SX CMT. PLUG AT 660' WITH 10 SX GEL & 50 SX CMT. PLUG AT 390' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/23/2010 10:30 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 3300' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. 1ST PLUG AT 660' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 390' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3358	3491		LKC

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OILWELL CEMENTING.

Plugged through: CSG

District: 01

Signed Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED
AUG 30 2010
KCC DODGE CITY

RECEIVED
SEP 07 2010
KCC WICHITA