

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-22152-00-02  
Spot: NESWNW Sec/Twnshp/Rge: 10-22S-12W  
3473 feet from S Section Line, 4364 feet from E Section Line  
Lease Name: SPANGENBERG Well #: 2-10  
County: STAFFORD Total Vertical Depth: 3664 feet

Operator License No.: 6170  
Op Name: GLOBE OPERATING, INC.  
Address: PO BOX 12  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3480		
SURF	8.625	250		WITH 225 SX CMT
PROD	5.5	3662	1582	WITH 175 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/19/2010 10:30 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: TOM DICKSON Company: D S & W WELL SERVICING, INC. Phone: (620) 793-5838

Proposed Plugging Method: SAND TO 3300' & 5 SX CMT. PLUG AT 660' WITH 10 SX GEL & 50 SX CMT. PLUG AT 280' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/19/2010 1:05 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SAND BACK TO 3300' & PUT 5 SX CMT ON TOP OF SAND BRIDGE. 1ST PLUG AT 660' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 280' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3365	3494		LKC

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

Plugged through: CSG

District: 01

RECEIVED

AUG 30 2010

KCC DODGE CITY

Signed

*Stephen J. Pfeifer*

(TECHNICIAN)

RECEIVED

SEP 07 2010

KCC WICHITA

Form SP-373