

TO: ✓
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-23900-00-00
Spot: NENWSWSE Sec/Twnshp/Rge: 30-6S-18W
1090 feet from S Section Line, 2070 feet from E Section Line
Lease Name: MAYHEW Well #: 1-30
County: ROOKS Total Vertical Depth: 3611 feet

Operator License No.: 33906
Op Name: GNAD OIL LLC
Address: PO BOX 580
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	223		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/06/2010 6:00 AM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM ALM Company: GNAD OIL LLC Phone: (785) 625-5768

Proposed Plugging Method: Ordered 245 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: PAT STAAB Witness Type: NONE
Date/Time Plugging Completed: 11/06/2010 7:00 AM KCC Agent: PAT STAAB

Actual Plugging Report:

1st. Plug at 3510' w/25 sxs.
2nd. Plug at 1545' w/25 sxs.
3rd. Plug at 904' w/100 sxs.
4th. Plug at 273' w/40 sxs.
5th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.
Mousehole with 15 sxs.


Perfs:

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed _____



(TECHNICIAN)

CM

RECEIVED

NOV 17 2010

Form CP-2/3

NOV 12 2010

KCC WICHITA