

TO: ✓  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-22742-00-01  
Spot: NWSESW Sec/Twnshp/Rge: 24-10S-20W  
990 feet from S Section Line, 1650 feet from W Section Line  
Lease Name: SUTOR D Well #: 1  
County: ROOKS Total Vertical Depth: 3696 feet

Operator License No.: 6931  
Op Name: BOWMAN OIL COMPANY, A GENERAL  
Address: 805 CODELL RD  
CODELL, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3680		WIRELINE PLUG
SURF	8.625	305	0	215 SX CMT
PLG		3680		
PROD	4.5	3693	0	150 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/19/2010 10:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: DONALD A. BOWMAN Company: BOWMAN OIL COMPANY, A GENE Phone: (785) 434-2286

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls.  
Perf two holes each at 1850' - 1550' - 900'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/19/2010 1:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated two holes each at 1850' - 1550' - 900'.  
Ran tubing to 2000'. Quality Oil Well Cementing pumped 100 sxs 60/40 pozmix - 4% gel with 250# hulls.  
Pulled tubing to 1000'. Quality Oil Well Cementing pumped 70 sxs 60/40 pozmix - 4% gel with 250# hulls - cement circulated.  
PTOH. Squeezed 10 sxs cement.  
Max. P.S.I. 800#. S.I.P. 500#.  
Hooked up to backside - instant pressure.

Perfs:

Top	Bot	Thru	Comments
3542	3546		KANSAS CITY

RECEIVED  
NOV 29 2010  
KCC WICHITA

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Richard Williams  
(TECHNICIAN)

CM

Form CP-2/3

NOV 24 2010