

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-109-20951-00-00
Spot: W2NWNWSE Sec/Twnshp/Rge: 36-15S-33W
2310 feet from S Section Line, 2541 feet from E Section Line
Lease Name: FAIRLEIGH "B" Well #: 1-36
County: LOGAN Total Vertical Depth: 4728 feet

Operator License No.: 4629
Op Name: BRITO OIL COMPANY, INC.
Address: 1700 N WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	243		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/22/2010 1:00 PM
Plug Co. License No.: 6039 Plug Co. Name: L.D. DRILLING, INC.
Proposal Rcvd. from: RICK WILSON Company: BRITO OIL COMPANY, INC. Phone: (316) 263-8787

Proposed Plugging Method: Ordered 205 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: EDWIN SCHUMACHER WitnessType: NONE
Date/Time Plugging Completed: 11/22/2010 3:15 PM KCC Agent: EDWIN SCHUMACHER

Actual Plugging Report:

1st. Plug at 2385' w/25 sxs.
2nd. Plug at 1100' w/100 sxs.
3rd. Plug at 300' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.

Perfs:

RECEIVED
NOV 29 2010
KCC WICHITA

Remarks: SWIFT CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed Ed Schumacher
(TECHNICIAN)

CM

Form CP-2/3

NOV 23 2010