

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-075-20130-00-00
Spot: SENW Sec/Twnshp/Rge: 14-21S-40W
3249 feet from S Section Line, 3229 feet from E Section Line
Lease Name: FRACK Well #: 1-14
County: HAMILTON Total Vertical Depth: 2805 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: 6200 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2399		WITH 2 SX CMT
SURF	8.625	305		WITH 250 SX CMT
PROD	4.5	2804	0	WITH 500 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/12/2010 1:00 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/12/2010 5:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

TBG STUCK. SHOT TBG OFF @ 2400'. CIBP @ 2399' WITH 2 SX CMT. FLUID LEVEL = 1500'. LOADED CASING & PRESSURED TO 300#. NO CASING LEAK. RAN BOND LOG. TOC @ 298'. RAN TBG TO 1275'. CIRCULATE 4 1/2" CASING FULL OF CMT IN 2 STAGES WITH 85 SX CMT. TOOH WITH TBG. TOP OFF 4 1/2" WITH 2 SX CMT. PUMP 15 SX CMT DOWN 4 1/2" X 8 5/8" ANNULUS. SHUT IN PRESSURE 200#.

Perfs:

Top	Bot	Thru	Comments
2746	2752		WINFIELD

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED
NOV 19 2010
KCC DODGE CITY

Signed

Ken Jehlik

(TECHNICIAN)

RECEIVED
DEC 01 2010

KCC WICHITA

Form CR-23