

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-103-20224-00-00  
Spot: SENWNWSW Sec/Twnshp/Rge: 25-7S-21E  
2230 feet from S Section Line, 4873 feet from E Section Line  
Lease Name: E T WILKES Well #: 2  
County: LEAVENWORTH Total Vertical Depth: 1511 feet

Operator License No.: 31819  
Op Name: CHOLLA PRODUCTION, LLC  
Address: 7851 S ELATI ST STE 201  
LITTLETON, CO 80120

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1400		
SURF	11.25	89		55 SX
PROD	6.5	1511		210 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/21/2010 9:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: VANE HUGGINS Company: CHOLLA PRODUCTION, LLC Phone: (913) 773-8154

Proposed Plugging Method: CEMENT PLUGS AS FOLLOWS: FROM BRIDGE PLUG AT 1400 TO 1296; FROM 361' TO SURFACE (TOP KANSAS CITY AT 361).

Plugging Proposal Received By: TAYLOR HERMAN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/21/2010 12:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

HOOKED ON TO 6.5" PRODUCTION CASING AND PUMPED 15 POUNDS OF COTTON SEED HULLS AHEAD OF 99 SACKS OF CEMENT. THE WELL WAS SHUT-IN AT 1200 POUNDS PSI.

Perfs:

Top	Bot	Thru	Comments
1404	1411		M CLOUTH SAND
1380	1383		PENNSYLVANIAN
1373	1376		PENNSYLVANIAN
1346	1350		PENNSYLVANIAN

RECEIVED

NOV 17 2010 TCH

KCC Chanute Dist. #3

RECEIVED

NOV 19 2010

KCC WICHITA

Remarks:

Plugged through: CSG

District: 03

Signed

Taylor C. Herman

(TECHNICIAN)