

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-21672-00-00
Spot: SWSESW Sec/Twnshp/Rge: 1-23S-31W
342 feet from S Section Line, 3602 feet from E Section Line
Lease Name: TREKELL Well #: 2-1
County: FINNEY Total Vertical Depth: 4906 feet

Operator License No.: 5663
Op Name: HESS OIL COMPANY
Address: PO BOX 1009
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1870		
CIBP		4735		WITH 2 SX CMT
SURF	8.625	480		WITH 275 SX CMT
DVT		1840		WITH 275 SX CMT
PROD	4.5	4906	0	WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/17/2010 9:30 AM
Plug Co. License No.: 5663 Plug Co. Name: HESS OIL COMPANY
Proposal Revd. from: ARNIE HESS Company: HESS OIL COMPANY Phone: (620) 241-4640

Proposed Plugging Method: CIBP @ 4740' WITH 2 SX CMT. CIBP @ 1870'. CIRCULATE CMT TO SURFACE FROM 1870'. CHECK BACKSIDE WITH 50 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/17/2010 3:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CASING LEAKS 4600' TO 4716'. CIBP @ 4735' WITH 2 SX CMT. CIBP @ 1870'.
FILL 4 1/2" CASING WITH CMT FROM 1850' TO 0' IN 2 STAGES USING 115 SX CMT.
FULL CIRCULATION. PUMP 6 SX CMT DOWN ANNULUS TO 250#.

Perfs:

Top	Bot	Thru	Comments
4790	4796		MISSISSIPPI

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED

NOV 24 2010

KCC DODGE CITY

Signed

Ken Jehlik

(TECHNICIAN)

RECEIVED

DEC 10 2010

KCC WICHITA

Form CP-2/3