

TO: ✓
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-03311-00-00
Spot: N2SESW Sec/Twnshp/Rge: 14-16S-12W
990 feet from S Section Line, 3300 feet from E Section Line
Lease Name: MARTHA OESER Well #: 1
County: BARTON Total Vertical Depth: 3352 feet

Operator License No.: 6296
Op Name: HOLT, IVAN LEROY DBA LEROY HOLT
Address: PO BOX 30503
EDMOND, OK 73003

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| SURF | 8.625 | 241 | 0 | 150 SX |
| PROD | 5.5 | 3339 | 0 | 100 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/04/2010 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: TODD BROWN Company: LEROY HOLT OIL OPERATIONS Phone: (785) 483-2822

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls - 9 sxs gel.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/04/2010 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Squeezed backside from 1700' to surface.
Ran tubing to 3000' - pumped 9 sxs gel - followed with 50 sxs cement and 200# hulls.
Pulled tubing to 1600' - pumped 140 sxs cement with 300# hulls - circulated cement to surface.
Pulled tubing - tied to casing and pumped 25 sxs cement.
Max. P.S.I. 500#. S.I.P. 300#.
Backside full of cement.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3190 | 3194 | | |
| 3126 | 3130 | | |
| 3099 | 3102 | | |

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

RECEIVED

CM

NOV 17 2010 Form CP-2/3

KCC WICHITA

NOV 15 2010