

TO: ✓  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-071-20839-00-00  
Spot: SESENW Sec/Twnshp/Rge: 13-19S-41W  
2300 feet from N Section Line, 2300 feet from W Section Line  
Lease Name: CAMPBELL Well #: 4-13  
County: GREELEY Total Vertical Depth: 2966 feet

Operator License No.: 4894  
Op Name: HORSESHOE OPERATING, INC.  
Address: 110 W LOUISIANA STE 200  
MIDLAND, TX 79701

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	236		WITH 175 SX CMT
PROD	4.5	2966	0	WITH 650 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/28/2010 10:30 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: DAVE OLSON Company: HORSESHOE OPERATING Phone: (620) 376-8190

Proposed  
Plugging  
Method:

CHECK FL, IF OK PUMP 300# HULLS & 190 SX CMT. PUMP 100 SX CMT DOWN ANNULUS.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/28/2010 11:30 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

FILL 4 1/2" CASING WITH 300# HULLS & 190 SX CMT FROM 2933' TO SURFACE.  
PRESSURE TO 500#. SHUT IN PRESSURE 300#. PUMP 25 SX CMT DOWN  
ANNULUS. PRESSURED TO 400#. SHUT IN PRESSURE 400#.

Perfs:

Top	Bot	Thru	Comments
2919	2933		
2903	2908		
2887	2900		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

Signed \_\_\_\_\_

*Ken Jehlik*

(TECHNICIAN)

RECEIVED

AUG - 2 2010

KCC DODGE CITY

RECEIVED

AUG 16 2010

KCC WICHITA

Form CP-102