

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-071-20665-00-00
Spot: SENE Sec/Twnshp/Rge: 16-20S-40W
1980 feet from N Section Line, 660 feet from E Section Line
Lease Name: COUPLAND Well #: 1-A
County: GREELEY Total Vertical Depth: 2854 feet

Operator License No.: 4894
Op Name: HORSESHOE OPERATING, INC.
Address: 110 W LOUISIANA STE 200
MIDLAND, TX 79701

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	290		WITH 175 SX CMT
PROD	4.5	2853	0	WITH 525 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/28/2010 8:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DAVE OLSON Company: HORSESHOE OPERATING Phone: (620) 376-8190

Proposed Plugging Method: CHECK FL. IF OK PUMP 300# HULLS & 190 SX CMT. PUMP 100 SX CMT DOWN ANNULUS

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/28/2010 10:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

FILL 4 1/2" CASING WITH 300# HULLS & 180 SX CMT FROM 2834' TO SURFACE.
PRESSURE TO 500#. SHUT IN PRESSURE 300#. PUMP 40 SX CMT DOWN ANNULUS
& PRESSURE TO 300#. SHUT IN PRESSURE 250#.

Perfs:


Top	Bot	Thru	Comments
2814	2834		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)

RECEIVED
AUG - 2 2010
KCC DODGE CITY

RECEIVED
AUG 16 2010
KCC WICHITA