

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-071-20594-00-02
Spot: SWSW Sec/Twnshp/Rge: 27-17S-40W
660 feet from S Section Line, 660 feet from W Section Line
Lease Name: LEE Well #: 2-27
County: GREELEY Total Vertical Depth: 3010 feet

Operator License No.: 4894
Op Name: HORSESHOE OPERATING, INC.
Address: 110 W LOUISIANA STE 200
MIDLAND, TX 79701

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	279		WITH 200 SX CMT
PROD	4.5	3009	0	WITH 600 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/28/2010 12:15 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DAVE OLSON Company: HORSESHOE OPERATING Phone: (620) 376-8190

Proposed
Plugging
Method:

CHECK FL. IF OK PUMP 400# HULLS & 190 SX CMT. PUMP 100 SX CMT DOWN ANNULUS.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/28/2010 1:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

FILL 4 1/2" CASING WITH 30 BALL SEALERS, 300# HULLS, & 220 SX CMT FROM 2978' TO 0'. PRESSURE TO 400#. SHUT IN PRESSURE 250#. PUMP 15 SX CMT DOWN ANNULUS TO 200#. STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
2944	2978		
2890	2910		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: DP

District: 01

Signed



(TECHNICIAN)

RECEIVED
AUG - 2 2010
KCC DODGE CITY

RECEIVED
AUG 16 2010
KCC WICHITA

Form 10-3/3