

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-25471-00-00
Spot: SENWNW Sec/Twnshp/Rge: 16-16S-13W
990 feet from N Section Line, 990 feet from W Section Line
Lease Name: WITTIG-SHELTON Well #: 4
County: BARTON Total Vertical Depth: 3388 feet

Operator License No.: 30380
Op Name: HUPFER OPERATING, INC.
Address: PO BOX 3912
SHAWNEE, KS 66203

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| SURF | 8.625 | 477 | | |

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/16/2010 5:00 PM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM ALM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: Ordered 205 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: PAT STAAB WitnessType: NONE
Date/Time Plugging Completed: 10/16/2010 5:45 PM KCC Agent: PAT STAAB

Actual Plugging Report:

1st. Plug at 3350' w/25 sxs.
2nd. Plug at 892' w/25 sxs.
3rd. Plug at 524' w/100 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.
Mousehole with 15 sxs.

Perfs:

Remarks: BASIC CEMENTING COMPANY.

Plugged through: DP

RECEIVED
OCT 25 2010
KCC WICHITA

District: 04

Signed [Signature]
(TECHNICIAN)

CM