

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-25484-00-00
Spot: SWNWNE Sec/Twnshp/Rge: 16-14S-20W
990 feet from N Section Line, 2140 feet from E Section Line
Lease Name: SHELBY Well #: 16-1
County: ELLIS Total Vertical Depth: 3915 feet

Operator License No.: 33335
Op Name: IA OPERATING, INC.
Address: 9915 W 21ST ST, STE B
WICHITA, KS 67205

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-------------|
| SURF | 8.625 | 219 | 0 | 150 SX CMT. |
| T1 | 2.875 | 3763 | | |
| PC | | 1537 | | |
| PROD | 5.5 | 3913 | 0 | 150 SX CMT. |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/14/2010 10:00 AM
Plug Co. License No.: 32028 Plug Co. Name: CHITO'S WELL SERVICE, LLC
Proposal Rcvd. from: MIKE STANTON Company: IA OPERATING, INC. Phone: (316) 721-0036

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 500# hulls - 18 sxs gel spacer.
Prod. Perfs 3842' - 3843'.
Port collar at 1537' w/200 sxs cwc.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/14/2010 1:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3795' - pumped 18 sxs gel spacer - followed with 50 sxs 60/40 pozmix - 4% gel with 200# hulls.
Pulled tubing to 1561' - pumped 150 sxs 60/40 pozmix - 4% gel to circulate to surface.
Pulled all tubing. Topped off 5 1/2" casing with 30 sxs 60/40 pozmix - 4% gel.
Hooked to 8 5/8" x 5 1/2" annulus. Pressured to 200# immediately.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3812 | 3818 | | |
| 3657 | 3660 | | |
| 3532 | 3540 | | |

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #4500.

Plugged through: TBG

District: 04

Signed _____

Pat Bedore
(TECHNICIAN)

RECEIVED

SEP 20 2010

CM

KCC WICHITA

Form CP-2/3

SEP 14 2010