

TO: ✓  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-20795-00-01  
Spot: NESENW Sec/Twnshp/Rge: 27-24S-12W  
3630 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: BYER Well #: 3  
County: STAFFORD Total Vertical Depth: 4119 feet

Operator License No.: 33527  
Op Name: J D DREILING OIL, INC.  
Address: 215 6TH ST  
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	324		
LI	4.5	2700		
PROD	5.5	4110	0	

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/01/2010 8:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: CASING PARTED @ 3200'. RUN TO 3800' & PUMP 75 SX CMT. PERFORATE 5 1/2" @ 690' & CIRCULATE CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: NONE  
Date/Time Plugging Completed: 10/15/2010 1:15 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

RAN TBG TO 3800' & PUMPED 150# HULLS & 75 SX CMT. PERFORATED 5 1/2" @ 696'. PUMPED 75 SX CMT DOWN 5 1/2" & IT PRESSURED UP. PUMPED 20 SX CMT DOWN 5 1/2". PUMPED 100 SX CMT DOWN 8 5/8" X 5 1/2" ANNULUS. SHUT IN PRESSURED 200 PSIG.

Perfs:

Top	Bot	Thru	Comments
4070	4076		
3927	3931		
3915	3927		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

District: 01

Signed

Steve Durrant

RECEIVED  
OCT 22 2010  
KCC DODGE CITY

RECEIVED (NICIAN)  
OCT 27 2010  
KCC WICHITA