

TO: ✓
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-23706-00-00
Spot: NENENW Sec/Twnshp/Rge: 23-9S-23W
330 feet from N Section Line, 2310 feet from W Section Line
Lease Name: BRANDYBERRY Well #: 1
County: GRAHAM Total Vertical Depth: 3935 feet

Operator License No.: 33813
Op Name: JASON OIL COMPANY, LLC
Address: 3718- 83RD ST PO BOX 701
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	226		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 12/05/2010 9:00 AM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM ALM Company: JASON OIL COMPANY, LLC Phone: (785) 483-4204

Proposed Plugging Method: Ordered 220 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: BRUCE BASYE WitnessType: NONE
Date/Time Plugging Completed: 12/05/2010 11:15 AM KCC Agent: BRUCE BASYE

Actual Plugging Report:

1st. Plug at 1965' w/25 sxs.
2nd. Plug at 1145' w/100 sxs.
3rd. Plug at 270' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.
Mousehole with 15 sxs.


Perfs:

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed


(TECHNICIAN)

CM

RECEIVED

DEC 08 2010

Form CP-2/3

KCC WICHITA

DEC 06 2010