

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-20994-00-00
Spot: NWNWNW Sec/Twnshp/Rge: 15-32S-19W
330 feet from N Section Line, 330 feet from W Section Line
Lease Name: HAROLD HERD Well #: 2-15
County: COMANCHE Total Vertical Depth: 5300 feet

Operator License No.: 30313
Op Name: JHL ENERGY, INC.
Address: 229 S PRESCOTT ST
WICHITA, KS 67209

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|-----------------|
| CIBP | | 5000 | | WITH 2 SX CMT |
| CIBP | | 5182 | | |
| SURF | 8.625 | 728 | | WITH 400 SX CMT |
| COND | 20 | 90 | | |
| PROD | 4.45 | 5306 | 3317 | WITH 150 SX CMT |

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/04/2010 2:45 PM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: ALAN VRATIL Company: CLARKE CORPORATION Phone: (620) 886-2419

Proposed Plugging Method: CIBP @ 4995' WITH 2 SX CMT. PLUG AT 1070' WITH 15 SX GEL & 50 SX CMT. PLUG AT 750' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: NONE
Date/Time Plugging Completed: 10/04/2010 4:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 5000' WITH 2 SX CMT. 1ST PLUG AT 1070' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 750' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 40 SX CMT. CMT TO SURFACE.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|------------|
| 5097 | 5103 | | FORT SCOTT |

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY CEMENTING.

Plugged through: TBG

District: 01

RECEIVED
OCT - 7 2010
KCC DODGE CITY

Signed

Ken Jehlik
(TECHNICIAN)

RECEIVED
OCT 15 2010
KCC WICHITA

Form CP-2/3