

TO: ✓
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-21021-00-00
Spot: SENEW Sec/Twnshp/Rge: 18-9S-23W
1650 feet from S Section Line, 2970 feet from E Section Line
Lease Name: ALBERTSON Well #: 2
County: GRAHAM Total Vertical Depth: 3902 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: 370 W WICHITA AVE PO BOX 352
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	202	0	w/160 sxs cmt
T1	2	3885		
PKR		3902		
PROD	4.5	3989	0	w/150 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/04/2010 10:00 AM
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC
Proposal Rcvd. from: DUANE EICHMAN Company: FARMER, JOHN O., INC. Phone: (785) 483-8355

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls.
DV Tool at 2075' w/350 sxs.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/04/2010 1:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 2500' - pumped 175 sxs 60/40 pozmix - 4% gel with 200# hulls.
Pulled tubing to 1250' - pumped 60 sxs 60/40 pozmix - 4% gel to circulated to surface.
Pulled all tubing. Topped off 4 1/2" casing with 15 sxs 60/40 pozmix - 4% gel.
Hooked to 8 5/8" x 4 1/2" annulus - pumped 15 sxs 60/40 pozmix - 4% gel.
Max. P.S.I. 400#.

Perfs:

Top	Bot	Thru	Comments
3890	3894		

Remarks: ALLIED CEMENTING COMPANY-TICKET #35147A.

Plugged through: TBG

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

CM

RECEIVED

NOV 17 2010

Form CP-2/3

NOV 12 2010

KCC WICHITA