

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-20294-00-00
Spot: NESWNW Sec/Twnshp/Rge: 23-29S-13W
3746 feet from S Section Line, 4189 feet from E Section Line
Lease Name: KINZIE Well #: SWD
County: PRATT Total Vertical Depth: 884 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: 370 W WICHITA AVE PO BOX 352
RUSSELL, KS 67665

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|-----------------|
| SURF | 8.625 | 200 | | WITH 200 SX CMT |
| PROD | 5.5 | 808 | 0 | WITH 200 SX CMT |

Well Type: SWD UIC Docket No: D18090.0 Date/Time to Plug: 11/16/2010 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: VAL DREHER Company: JOHN O. FARMER Phone: (785) 483-8356

Proposed Plugging Method: PUMP 200# HULLS & CMT FROM TOP TO BOTTOM & THEN PUMP BACKSIDE.

Plugging Proposal Received By: JERRY W. STAPLETON Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/16/2010 10:00 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PUMPED DOWN 5 1/2" CASING WITH 200# HULLS & 40 SX CMT. SQUEEZED AT 500#. SHUT IN AT 250#. PUMPED DOWN 5 1/2" X 8 5/8" ANNULUS WITH 8 SX CMT. BACKSIDE FULL. SHUT IN AT 600#.

Perfs:


| Top | Bot | Thru | Comments |
|-----|-----|------|------------------|
| 742 | 772 | | |
| 736 | 750 | | |
| 730 | 736 | | |
| 712 | 720 | | |
| 550 | 884 | | CEDAR HILLS- DIS |

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

Signed


(TECHNICIAN)

RECEIVED

NOV 22 2010

KCC DODGE CITY

RECEIVED

DEC 08 2010

KCC WICHITA

Form CP-23