

TO: ✓  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-20979-00-00  
Spot: NWNWSE Sec/Twnshp/Rge: 18-9S-23W  
2310 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: KLENK Well #: 2  
County: GRAHAM Total Vertical Depth: 3990 feet

Operator License No.: 5135  
Op Name: FARMER, JOHN O., INC.  
Address: 370 W WICHITA AVE PO BOX 352  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	217	0	w/160 sxs cmt
TI		3987		
PROD	5.5	3989	0	w/150 sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/05/2010 11:30 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: DUANE EICHMAN Company: FARMER, JOHN O., INC. Phone: (785) 483-8355

Proposed Plugging Method: Ordered out 450 sxs 60/40 pozmix - 4% gel - 500# hulls.  
DV at 2055' cwc.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/05/2010 1:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 2500'. Allied pumped 380 sxs 60/40 pozmix - 4% gel with 500# hulls.  
Pulled tubing to 1250'. Allied pumped 25 sxs cwc.  
PTOH. Topped 5 1/2" casing with 15 sxs.  
Hooked up to backside - pumped 5 sxs cement - instant pressure.  
Blew hole in 8 5/8". Full of cement.

Perfs:

Top	Bot	Thru	Comments
3930	3932		
3861	3864		
3822	3824		
3804	3808		
3776	3780		
3766	3770		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

RECEIVED

NOV 17 2010

Form CP-2/3

NOV 15 2010

KCC WICHITA