

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-147-20633-00-00  
Spot: NWNWSENW Sec/Twnshp/Rge: 21-4S-20W  
1570 feet from N Section Line, 1390 feet from W Section Line  
Lease Name: SCHOOLER A Well #: 1  
County: PHILLIPS Total Vertical Depth: 3581 feet

Operator License No.: 5135

Op Name: FARMER, JOHN O., INC.

Address: 370 W WICHITA AVE PO BOX 352  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	220		

Well Type: DH

UIC Docket No:

Date/Time to Plug: 10/02/2010 5:00 PM

Plug Co. License No.: 31548

Plug Co. Name: DISCOVERY DRILLING

Proposal Rcvd. from: TOM ALM

Company: FARMER, JOHN O., INC.

Phone: (785) 483-3144

Proposed Plugging Method: Ordered 245 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: DARREL DIPMAN

WitnessType: NONE

Date/Time Plugging Completed: 10/02/2010 6:30 PM

KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perfs:

1st. Plug at 3525' w/25 sxs.  
2nd. Plug at 1660' w/25 sxs.  
3rd. Plug at 985' w/100 sxs.  
4th. Plug at 270' w/40 sxs.  
5th. Plug at 40' w/10 sxs.  
Rathole with 30 sxs.  
Mousehole with 15 sxs.

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: DP

RECEIVED  
OCT 18 2010  
KCC WICHITA

District: 04

Signed Darrel Dipman  
(TECHNICIAN)

CM

Form CP-2/3

OCT 05 2010