

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-171-20771-00-00
Spot: N2NESE Sec/Twnshp/Rge: 3-18S-32W
2310 feet from S Section Line, 660 feet from E Section Line
Lease Name: HUEFTLE Well #: 9D-3-1832
County: SCOTT Total Vertical Depth: 5000 feet

Operator License No.: 33476
Op Name: FIML NATURAL RESOURCES, LLC
Address: 410 17TH ST STE 900
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	393		WITH 240 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 09/09/2010 11:30 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: GARY DOKE Company: FIML Phone: (303) 893-5073

Proposed Plugging Method: 1ST PLUG AT 2290' WITH 50 SX CMT. 2ND PLUG AT 1520' WITH 80 SX CMT. 3RD PLUG AT 750' WITH 40 SX CMT. 4TH PLUG AT 420' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: NONE
Date/Time Plugging Completed: 09/10/2010 1:45 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

1ST PLUG AT 2290' WITH 50 SX CMT. 2ND PLUG AT 1520' WITH 80 SX CMT. 3RD PLUG AT 750' WITH 40 SX CMT. 4TH PLUG AT 420' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: DP

District: 01

RECEIVED

SEP 22 2010

KCC DODGE CITY

Signed

Steve Dumont

RECEIVED (TECHNICIAN)

SEP 30 2010

KCC WICHITA