

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-171-20788-00-00  
Spot: SWNESENW Sec/Twnshp/Rge: 34-18S-31W  
1950 feet from N Section Line, 2200 feet from W Section Line  
Lease Name: SUPPES Well #: 6A-34-1831  
County: SCOTT Total Vertical Depth: 4800 feet

Operator License No.: 33476  
Op Name: FIML NATURAL RESOURCES, LLC  
Address: 410 17TH ST STE 900  
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	398		WITH 240 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/07/2010 7:15 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: GARY DOKE Company: FIML Phone: (303) 893-5073

Proposed Plugging Method: 1ST PLUG AT 2280' WITH 50 SX CMT. 2ND PLUG AT 1470' WITH 80 SX CMT. 3RD PLUG AT 720' WITH 50 SX CMT. 4TH PLUG AT 420' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: NONE  
Date/Time Plugging Completed: 12/07/2010 9:15 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

1ST PLUG AT 2280' WITH 50 SX CMT. 2ND PLUG AT 1470' WITH 80 SX CMT. 3RD PLUG AT 720' WITH 50 SX CMT. 4TH PLUG AT 420' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

Signed Eric MacLaren  
(TECHNICIAN)

RECEIVED  
DEC - 8 2010  
KCC DODGE CITY

RECEIVED  
DEC 10 2010  
KCC WICHITA

Form CP-20