

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-137-20526-00-00  
Spot: NE Sec/Twnshp/Rge: 13-5S-22W  
2150 feet from N Section Line, 1260 feet from E Section Line  
Lease Name: ERICKSON Well #: 42-13  
County: NORTON Total Vertical Depth: 3650 feet

Operator License No.: 34038  
Op Name: FLATIRONS RESOURCES LLC  
Address: 303 E 17TH AVE STE 940  
DENVER, CO 80203

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	218		

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/15/2010 4:00 PM  
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC  
Proposal Rcvd. from: JAY Company: FLATIRONS RESOURCES LLC Phone: (303) 292-3902

Proposed Plugging Method: Ordered 205 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: BRUCE BASYE WitnessType: NONE  
Date/Time Plugging Completed: 09/15/2010 5:00 PM KCC Agent: BRUCE BASYE

Actual Plugging Report:

1st. Plug at 1780' w/25 sxs.  
2nd. Plug at 1030' w/100 sxs.  
3rd. Plug at 270' w/40 sxs.  
4th. Plug at 40' w/10 sxs.  
Rathole with 30 sxs.

Perfs:

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: DP

RECEIVED  
SEP 24 2010  
KCC WICHITA

District: 04

Signed Bruce D. Basye  
(TECHNICIAN)

CM

Form CP-2/3

SEP 16 2010