

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-23687-00-00  
Spot: NWSENE Sec/Twnshp/Rge: 28-6S-22W  
750 feet from N Section Line, 490 feet from E Section Line  
Lease Name: ROBERTS Well #: 41-28  
County: GRAHAM Total Vertical Depth: 3850 feet

Operator License No.: 34038  
Op Name: FLATIRONS RESOURCES LLC  
Address: 303 E 17TH AVE STE 940  
DENVER, CO 80203

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	262		

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/22/2010 6:00 PM  
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC  
Proposal Revd. from: DUSTY RHOADES Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: Ordered 205 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: PAT STAAB WitnessType: NONE  
Date/Time Plugging Completed: 10/22/2010 7:15 PM KCC Agent: PAT STAAB

Actual Plugging Report:

1st. Plug at 2002' w/25 sxs.  
2nd. Plug at 1222' w/100 sxs.  
3rd. Plug at 312' w/40 sxs.  
4th. Plug at 40' w/10 sxs.  
Rathole with 30 sxs.


Perfs:

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed \_\_\_\_\_

  
(TECHNICIAN)

CM

RECEIVED Form CP-2/3

NOV 01 2010

OCT 25 2010

KCC WICHITA