

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-23681-00-00
Spot: E2W2NE Sec/Twnshp/Rge: 29-29S-5E
4050 feet from S Section Line, 1691 feet from E Section Line
Lease Name: FLOWERS POTTORFF Well #: 1-29
County: BUTLER Total Vertical Depth: 2910 feet

Operator License No.: 6407
Op Name: FLOWERS PRODUCTION CO., INC.
Address: PO BOX 249
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	210		125 SX
T1	2.375	2859		
PROD	4.5	2909		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/04/2010 8:00 AM
Plug Co. License No.: 32701 Plug Co. Name: C & G DRILLING, INC.
Proposal Rcvd. from: DALLAS FLOWERS Company: FLOWERS PRODUCTION CO Phone: (316) 321-0550

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 11/04/2010 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 2794', CONSOLIDATED MIXED & PUMPED 25 SXS 60/40 POZMIX 4% GEL. 3% CC & DISPLACED IN CASING. TAGGED CEMENT @ 2810'. RIH W/RUBBER PLUG & TBG @ 2700'. CONSOLIDATED MIXED & PUMPED 20 SXS 60/40 POZMIX 4% GEL. 3% CC, & DISPLACED IN CASING. TAGGED CEMENT @ 2271'. PRESSURED CASING, HELD OK. SHOT CEMENT SQUEEZE HOLES @ 260'-261'. SWEDGED INTO 4-1/2" CASING. ESTABLISHED CIRCULATION & CONSOLIDATED MIXED & PUMPED 90 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED PLUG DOWN 11-4-2010, 5:00 P.M. CONSOLIDATED CEMENT TICKET #29224.

Perfs:

Top	Bot	Thru	Comments
2812	2816	CSG	
2801	2806	CSG	

Remarks:

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)

RECEIVED
NOV 17 2010
KCC WICHITA

Form CP-2/3