

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-22407-00-01  
Spot: S2NWSE Sec/Twnshp/Rge: 23-19S-10W  
1628 feet from S Section Line, 1973 feet from E Section Line  
Lease Name: JENKINS Well #: 1-23  
County: RICE Total Vertical Depth: 1569 feet

Operator License No.: 33725  
Op Name: FOUNDATION ENERGY MANAGEMEN  
Address: 14800 LANDMARK BLVD STE 220  
DALLAS, TX 75254

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	232		195 sx
PROD	4.5	1569		185 sx

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/15/2010 1:00 PM  
Plug Co. License No.: 32098 Plug Co. Name: CLASSIC WELL SERVICE, INC.  
Proposal Rcvd. from: KENT STRUBE Company: FOUNDATION ENERGY MGMT, LL Phone: (620) 786-4161

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: SHANE JONES WitnessType: PARTIAL  
Date/Time Plugging Completed: 09/15/2010 3:15 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. PERFORATE AT 1200', 850' AND 282'. RUN TUBING TO 1460' AND PUMP 25 SX'S CEMENT WITH COTTON HULLS. PULL TUBING TO 1200' AND PUMP 35 SX'S CEMENT. PULL TUBING TO 850' AND PUMP 35 SX'S CEMENT. PULL TUBING TO 282' AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF. USED 215 SX'S TOTAL. TOPPED OFF WITH 20 MORE SX'S CEMENT ON 9-22-2010 - COPELAND C-35118.

Perfs:

Top	Bot	Thru	Comments
1385	1418	CSG	

Remarks: USED 145 SX'S 60-40 POZ, 4% GEL AND 70 SX'S COMMON. GRESSELL PERF TICKET 0744. COPELAND TICKET C-35111. GPS -- 1643 F&L, 1989 FEL.

Plugged through: TBG

District: 02

Signed

Virgil Clothier

(TECHNICIAN)

RECEIVED

OCT 12 2010

Form CP-2/3

KCC WICHITA