

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-187-20921-00-00
Spot: W2NENW Sec/Twnshp/Rge: 29-30S-42W
650 feet from N Section Line, 1640 feet from W Section Line
Lease Name: HEYEN Well #: 29-21
County: STANTON Total Vertical Depth: 5647 feet

Operator License No.: 32426
Op Name: H & L OPERATING CO., L.L.P.
Address: PO BOX 7506
AMARILLO, TX 79114

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3650		WITH 10 SX CMT
CIBP		4900		WITH 10 SX CMT
SURF	9.625	1550		WITH 555 SX CMT
LI	4.5	5647		TOP @ 4998' W/70 SX
PROD	7	5250	0	WITH 425 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/07/2011 1:00 PM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: SET CIBP @ 4900' WITH 10 SX CMT. SET CIBP @ 3650' WITH 10 SX CMT. PLUG AT 1600' WITH 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT. CHECK BACKSIDE.

Plugging Proposal Received By: STEVE DURRANT Witness Type: NONE
Date/Time Plugging Completed: 04/08/2011 4:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

SET CIBP @ 4900' WITH 10 SX CMT. SET CIBP @ 3650' WITH 10 SX CMT. 1ST PLUG AT 1600' WITH 50 SX CMT. 2ND PLUG AT 600' WITH 100 SX CMT FILLING CASING TO SURFACE. 3RD PLUG PUMP 10 SX CMT DOWN 7 " X 9 5/8" ANNULUS. PRESSURED TO 500 PSI.

Perfs:

Top	Bot	Thru	Comments
5386	5396		
5368	5378		
5213	5346		
4194	4202		MARMATON
3693	3698		LANSING

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

RECEIVED
APR 25 2011

KCC WICHITA

District: 01

RECEIVED

APR 19 2011

KCC DODGE CITY

Signed

Jack MacLaskey
(TECHNICIAN)