

✓  
TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-055-22098-00-00  
Spot: NWNESESE Sec/Twnshp/Rge: 16-22S-33W  
1030 feet from S Section Line, 360 feet from E Section Line  
Lease Name: WARD TWIN Well #: 11  
County: FINNEY Total Vertical Depth: 4800 feet

Operator License No.: 30535  
Op Name: HARTMAN OIL CO., INC.  
Address: 10500 E BERKELEY SQ PKWY STE 100  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1780		WITH 575 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/26/2011 1:00 AM  
Plug Co. License No.: 33793 Plug Co. Name: H2 DRILLING LLC  
Proposal Rcvd. from: STEVE CRAIG Company: H2 DRILLING LLC Phone: (620) 636-2090

Proposed Plugging Method: 1ST PLUG AT 1810' WITH 50 SX CMT. 2ND PLUG AT 1100' WITH 40 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: NONE  
Date/Time Plugging Completed: 04/26/2011 3:00 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

1ST PLUG AT 1810' WITH 50 SX CMT. 2ND PLUG AT 1100' WITH 40 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: DP

District: 01

Signed

Richard W. Lacey

(TECHNICIAN)

RECEIVED

APR 26 2011

KCC DODGE CITY

RECEIVED

APR 28 2011

KCC WICHITA

Form 67P-2/3