

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-203-20154-00-00
Spot: SENENWSE Sec/Twnshp/Rge: 32-19S-38W
2306 feet from S Section Line, 1368 feet from E Section Line
Lease Name: NICKELSON Well #: 1
County: WICHITA Total Vertical Depth: 5150 feet

Operator License No.: 34314
Op Name: JAMEX, INC.
Address: 2871 LAKE VISTA DR., #200
LEWISVILLE, TX 75067

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	273		WITH 175 SX CMT
PROD	4.5	3148	0	WITH 1050 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/08/2011 10:00 AM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: TIM THOMPSON Company: JAMEX INC. Phone: _____

Proposed Plugging Method: FILL UP WITH CEMENT WITH 200# - 300# COTTON SEED HULLS AHEAD OF CEMENT

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/08/2011 2:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

FILL 4 1/2" CASING WITH CMT FROM 2854' TO 0' USING 50 7/8" BALLSEALERS, 100# HULLS & 175 SX CMT. PRESSURE TO 600#. HOLDING AT 500#. PUMP 5 SX CMT DOWN ANNULUS TO 600#.

Perfs:


Top	Bot	Thru	Comments
2852	2854		WINFIELD
2840	2843		WINFIELD
2832	2836		WINFIELD
2826	2828		WINFIELD
2796	2803		WINFIELD
2790	2792		WINFIELD

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)

RECEIVED
APR 18 2011
KCC DODGE CITY

RECEIVED
APR 28 2011

KCC WICHITA

Form CP-273