

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-02791-00-00
Spot: SWSENW Sec/Twnshp/Rge: 12-23S-4W
2970 feet from S Section Line, 3630 feet from E Section Line
Lease Name: NEUFELD Well #: 2
County: RENO Total Vertical Depth: 3440 feet

Operator License No.: 7116
Op Name: KANTOR OIL COMPANY, LLC
Address: 15 W 6TH ST STE 2601
TULSA, OK 74119

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3330		
SURF	12.5	497		400 SX
PROD	7	3440	702	400 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 8253 Plug Co. Name: G & L WELL SERVICE, INC.
Proposal Rcvd. from: LARRY RESSLER Company: _____ Phone: (620) 664-0597

Proposed AS PER KCC REQUIREMENTS.
Plugging
Method:

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL
Date/Time Plugging Completed: 10/22/2010 5:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

BOTTOM WAS SANDED BACK TO 3300 & TOP WITH 2 SX CEMENT 7 INCH CASING PARTED @ 702' - RAN IN WITH TUBING AFTER PULLING 7" CASING. PUMPED 100 SX COMMON CEMENT. W/300 LBS HULL & 4% CC, WAITED 2 HOURS TAGGED AT 505' - RAN ANOTHER 175 SX COMMON CEMENT W/300 LBS HULLS - SET OVERNIGHT, - TAG CEMENT @120' INSIDE PIPE. COULD NOT FIND CEMENT ON BACKSIDE OF SURFACE PIPE. PERF @ 112' AND CIRCULATED CEMENT AROUND SURFACE & FILLED INSIDE WITH A TOTAL OF 150 SX OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
3356	3363		

Remarks: DOWN MORE THAN 10 YEARS

Plugged through: TBG

District: 02

Signed

B. J. Hope

(TECHNICIAN)

RECEIVED
APR 27 2011
KCC WICHITA