

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-025-21495-00-00  
Spot: SESWNW Sec/Twnshp/Rge: 20-33S-25W  
2310 feet from N Section Line, 1020 feet from W Section Line  
Lease Name: THEIS Well #: 1-20  
County: CLARK Total Vertical Depth: 7256 feet

Operator License No.: 5254  
Op Name: MIDCO EXPLORATION, INC.  
Address: 414 PLAZA DR STE 204  
WESTMONT, IL 60559

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5070		WITH 2 SX CMT
CIBP		6960		
CIBP		7020		
SURF	8.625	882		WITH 400 SX CMT
COND	20	76		WITH 70 SX CMT
PROD	5.5	7253	3193	WITH 300 SX CMT

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/04/2011 10:00 AM  
Plug Co. License No.: 32297 Plug Co. Name: SUPERIOR SERVICING, INC.  
Proposal Revd. from: DAVID MAYFIELD Company: MIDCO EXPLORATION Phone: (620) 786-9165

Proposed Plugging Method: CIBP @ 5070' & 2 SX CMT. PLUG AT 910' WITH 15 SX GEL & 50 SX CMT. PLUG AT 300' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/04/2011 2:00 PM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

1ST PLUG SET CIBP @ 5070' & 2 SX CMT. 2ND PLUG TIHWT TO 927'. PUMP 20 SX GEL & 75 SX CMT. NO RETURNS. 3RD PLUG WOC 2 HOURS. TIHWT TO 927' & PUMP 35 SX GEL & 50 SX CMT. GOOD CIRCULATION. 4TH PLUG TBG TO 310' & PUMP 40 SX CMT. 5TH PLUG PULL TO 60' & PUMP 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
7030	7035		
6968	6970		
6878	6879		
6875	6877		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

RECEIVED  
APR 25 2011  
KCC WICHITA

District: 01

RECEIVED  
APR 18 2011

KCC DODGE CITY

Signed

Jerry W. Stapleton  
(TECHNICIAN)