

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-07179-00-00
Spot: NESENW Sec/Twnshp/Rge: 36-20S-14W
3630 feet from S Section Line, 2310 feet from W Section Line
Lease Name: WEST HISS LKC Well #: 4
County: BARTON Total Vertical Depth: 3478 feet

Operator License No.: 33190
Op Name: NOBLE ENERGY, INC.
Address: 1625 BROADWAY, STE 2200
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3200		
SURF	8.625	609	0	305 SX
PROD	5.5	3460	0	20 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/07/2011 11:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Revd. from: TOM KARST Company: NOBLE ENERGY, INC. Phone: (785) 625-4052

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls - 10 sxs gel.

RECEIVED
APR 25 2011
KCC WICHITA

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/07/2011 3:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfed at 1600' - 700' - 575'.
Ran tubing to 3156' - tied to tubing and pumped 10 sxs gel - followed with 50 sxs cement and 100# hulls.
Pulled tubing to 1707' - pumped 100 sxs cement with 200# hulls.
Pulled tubing to 703' - circulated to surface with 145 sxs cement on casing.
Pulled tubing - tied to casing and pumped 40 sxs cement - circulated out surface pipe.
S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
3444	3449		LKC

Remarks: BASIC ENERGY SERVICES.

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

Form CP-2/3

APR 11 2011