

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-083-21668-00-00
Spot: SENENWNW Sec/Twnshp/Rge: 36-22S-23W
402 feet from N Section Line, 1091 feet from W Section Line
Lease Name: HODGEMAN-O'BRATE Well #: 1-36
County: HODGEMAN Total Vertical Depth: 4477 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4400		WITH 2 SX CMT
SURF	8.625	268		WITH 170 SX CMT
PROD	5.5	4476	2015	WITH 150 SX CMT

Well Type: DH UIC Docket No: Date/Time to Plug: 02/04/2011 11:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Revd. from: JODY SMITH Company: AMERICAN WARRIOR Phone: (620) 272-1023

Proposed Plugging Method: SET CIBP @ 4400' WITH 2 SX CMT ON TOP. PLUG AT 1440' WITH 50 SX CMT. PLUG AT 660' WITH 80 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/04/2011 3:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4400' WITH 2 SX CMT. 1ST PLUG AT 1440' WITH 50 SX CMT. 2ND PLUG AT 660' WITH 80 SX CMT. 3RD PLUG AT 300' WITH 50 SX CMT. 4TH PLUG LAID LAST JOINT DOWN, STUCK HOSE IN 8 5/8" & PUMPED 200 SX CMT. CMT CONTINUED TO DROP. 2/22/11: TOPPED WELL OFF WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4459	4474		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

RECEIVED

APR 25 2011

KCC WICHITA

District: 01

Signed Eric MacLaren
(TECHNICIAN)

RECEIVED

APR 18 2011

KCC DODGE CITY

Form CR-28