

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-21504-00-00
Spot: SENE Sec/Twnshp/Rge: 8-27S-6W
3300 feet from S Section Line, 660 feet from E Section Line
Lease Name: WILKINSON Well #: 1
County: KINGMAN Total Vertical Depth: 4160 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	260		175 SX
PROD	4.5	4100	2440	275 SXS CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, INC.
Proposal Rcvd. from: GEORGE RAYL Company: _____ Phone: _____

Proposed Plugging Method: ACCORDING TO THE RULES AND REGULATIONS OF THE KCC.

Plugging Proposal Received By: JEFF KLOCK Witness Type: NONE
Date/Time Plugging Completed: 12/08/2010 12:00 AM KCC Agent: B. J. HOPE

Actual Plugging Report:

SET CIBP @ 3350 - TOPPED WITH 3 SX SHOT CASING OFF @ 2240'. PULLED CASING TO 969' SPOTTED 35 SX CEMENT PULLED CASING TO 510' SPOTTED 40 SX CEMENT. PULLED CASING TO 305' - CIRCULATED TO SURFACE WITH 135 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
3718	3722		MISSISSIPPI
3368	3370		KC

Remarks:

Plugged through: CSG

District: 02

Signed B. J. Hope
(TECHNICIAN)

RECEIVED
APR 27 2011
KCC WICHITA