

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-21492-00-00
Spot: SENEWSE Sec/Twnshp/Rge: 10-34S-21W
702 feet from S Section Line, 1626 feet from E Section Line
Lease Name: BOUZIDEN Well #: 1-10
County: CLARK Total Vertical Depth: 5633 feet

Operator License No.: 34131
Op Name: DAVID HOLKE CONSULTING, INC.
Address: 120 STONE FOREST PO BOX 1309
FREDERICKSBURG, TX 78624

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5400		WITH 2 SX CMT
CIBP		5490		
SURF	8.625	639		WITH 650 SX CMT
COND	20	75		
PROD	4.5	5628	4516	WITH 125 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/19/2011 2:00 PM
Plug Co. License No.: 32722 Plug Co. Name: KERR WELL SERVICE, INC.
Proposal Revd. from: ROGER PEARSON Company: PEARSON PETROLEUM CONSULTI Phone: (620) 629-1565

Proposed Plugging Method: CIBP @ 5400' WITH 2 SX CMT. PLUG AT 1100' WITH 15 SX GEL & 50 SX CMT. PLUG AT 660' WITH 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: JERRY W. STAPLETON Witness Type: NONE
Date/Time Plugging Completed: 04/19/2011 3:55 PM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

CIBP @ 5400' WITH 2 SX CMT. LOAD HOLE WITH MUD & CIRCULATE TO SURFACE. 1ST PLUG AT 1124' WITH 50 SX CMT. 2ND PLUG AT 664' WITH 50 SX CMT. 3RD PLUG AT 310' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 50 SX CMT. CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5495	5500		
5453	5470		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

RECEIVED

APR 25 2011

KCC DODGE CITY

Signed

Jerry W. Stapleton
PIETJE

(TECHNICIAN)

RECEIVED

APR 28 2011

KCC WICHITA