

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-069-20343-00-00
Spot: NWSESWSE Sec/Twnshp/Rge: 36-26S-28W
370 feet from S Section Line, 1890 feet from E Section Line
Lease Name: STRAWN Well #: 1-36
County: GRAY Total Vertical Depth: 5220 feet

Operator License No.: 8914
Op Name: H & C OIL OPERATING INC.
Address: PO BOX 86
PLAINVILLE, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	905		WITH 450 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 04/20/2011 3:00 AM

Plug Co. License No.: 33793 Plug Co. Name: H2 DRILLING LLC

Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: 1ST PLUG AT 1820' WITH 50 SX CMT. 2ND PLUG AT 930' WITH 50 SX CMT. 3RD PLUG AT 360' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER
Date/Time Plugging Completed: 04/20/2011 5:00 AM

WitnessType: NONE
KCC Agent: MICHAEL MAIER

Actual Plugging Report:

1ST PLUG AT 1820' WITH 50 SX CMT. 2ND PLUG AT 930' WITH 50 SX CMT. 3RD PLUG AT 360' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs: _____

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

Signed _____

Michael Maier
(TECHNICIAN)

RECEIVED

APR 21 2011

KCC DODGE CITY

RECEIVED

APR 28 2011

KCC WICHITA

Form CP-2/3