

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-26054-00-00
Spot: SEWNENESE Sec/Twnshp/Rge: 14-13S-16W
3070 feet from N Section Line, 911 feet from E Section Line
Lease Name: DORTLAND Well #: 14-1
County: ELLIS Total Vertical Depth: 3560 feet

Operator License No.: 6246
Op Name: BENNETT & SCHULTE OIL CO., A GEN
Address: 140 W. WICHITA AVE
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	229	0	w/150 sxs cmt
PROD	5.5	3543	1330	w/200 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/20/2011 10:15 AM
Plug Co. License No.: 33385 Plug Co. Name: J. & M WELL SERVICING, INC.
Proposal Rcvd. from: FRANK SCHULTE Company: BENNETT & SCHULTE OIL, CO. Phone: (785) 483-2721

Proposed Plugging Method: Ordered 360 sxs 60/40 pozmix - 4% gel - 500# hulls.
PBTD 3502'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/20/2011 6:45 PM KCC Agent: PAT STAAB

Actual Plugging Report:

J&M Well Service sanded off bottom to 2800' - topped with 5 sxs cement using a dump bailer.
Log Tech shot 5 1/2" casing at 1962'.
Pulled casing to 1700' - rigged to 5 1/2" casing and pumped 125 sxs cement with 300# hulls.
Pulled casing to 1025' - rigged to casing and pumped 40 sxs cement with 100# hulls.
Pulled one joint to 988' - casing got stuck in the hole - circulated out with 180 sxs cement.
Backed off casing - recovered a total of 35 joints 1330' - left 21 joints in the hole.
Topped off 8 5/8" with 10 sxs cement - hole standing full.

Perfs:

Top	Bot	Thru	Comments
3225	3227		
3161	3165		

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: CSG

RECEIVED

APR 25 2011

KCC WICHITA

District: 04

Signed _____

Frank Schulte
(TECHNICIAN)

CM

Form CP-2/3

APR 21 2011